

BRUHAT BANGALORE

BRUHAT BANGALORE MUNCIPALITY

Name of Work: Improvements to roads and drainage in ward no. 03. Attur

[illegible]

BRUHAT BANGALORE MAHANAGARA PALIKE

Name of Work: Improvements to roads and drain at cross and main roads in AMS Layout in ward no. 03, Attur

SI No	Description of work	Unit	No	Length m	Breadth m	Depth m	Quantity	Rate in Rs	Amount in Rs
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)								
	For RCC Drain	Cum							
	AMS Layout								
	3rd main		2	207.00	1.10	1.00	455.40		
	5th main		2	160.00	1.10	1.00	352.00		
	3rd cross		2	178.00	1.10	0.95	372.02		
	1st A cross		2	85.00	1.10	0.90	168.30		
	Culvert		2	6.60	1.50	0.90	17.82		
							1365.54	220.40	300965.02
	Basic Rate Rs.=	130.00							
	Add 6% A.W Rs. =	7.80							
	Sub Total =	137.80							
	8Km Lead, Loading and Unloading =(2*1.28*10)+57	82.60							
	Total Rate Rs. =	220.40							
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)								
	For Drain	Cum							
	AMS Layout								
	3rd main		2	207.00	1.10	0.15	68.31		
	5th main		2	160.00	1.10	0.15	52.80		
	3rd cross		2	178.00	1.10	0.15	58.74		
	1st A cross		2	85.00	1.10	0.15	28.05		
	Culvert		2	6.60	1.50	0.15	2.97		
							210.87	5421.90	1143316.05
	Basic Rate Rs.=	5115.00							
	Add 6% A.W Rs. =	306.90							
	Total Rate Rs. =	5421.90							
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete exeluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWT S.R 2018-19)								
	For RCC Drain	Cum							

SI No	Description of work	Unit	No	Length m	Breadth m	Depth m	Quantity	Rate in Rs	Amount in Rs
	Bottom slab								
	AMS Layout								
	3rd main		2	207.00	0.90	0.15	55.89		
	5th main		2	160.00	0.90	0.15	43.20		
	3rd cross		2	178.00	0.90	0.15	48.06		
	1st A cross		2	85.00	0.90	0.15	22.95		
	side walls								
	AMS Layout								
	3rd main		4	207.00	0.15	0.60	74.52		
	5th main		4	160.00	0.15	0.60	57.60		
	3rd cross		4	178.00	0.15	0.60	64.08		
	1st A cross		4	85.00	0.15	0.60	30.60		
	Culvert raft		2	6.60	1.20	0.20	3.17		
	Culvert wall		4	6.60	0.23	0.60	3.64		
							403.71		
						Net Qty.	403.71	7070.20	2854318.93
	Basic Rate Rs.=	6670.00							
	Add 6% A.W Rs. =	400.20							
	Total Rate Rs. =	7070.20							
4	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebtrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWT D S.R 2018-19)								
	Considering steel For Drain @ 60 kg / cum	Tonne		396.90	0.060	-	23.81		
	Considering steel For culvert @ 90 kg / cum	Tonne		6.81	0.090	-	0.61		
							24.43	73992.24	1807409.04
	Basic Rate Rs.=	69804.00							
	Add 6% A.W Rs. =	4188.24							
	Total Rate Rs. =	73992.24							
5	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
	For drain cover slab	Sqm							
	AMS Layout								
	8th cross, Left side		2	207.00	0.90	--	372.60		
	8th cross, Right side, LHS		2	160.00	0.90	--	288.00		
	8th cross, Right side, RHS		2	178.00	0.90	--	320.40		
	1st A cross		2	85.00	0.90	--	153.00		
							1134.00	2337.00	2650158.00
	Data Rate Rs. =	2337.00							

[illegible]

BRUHAT BANGALORE MAHANAGARA PALIKE

Name of Work: Improvements to roads and drain at 8th, 9th, 10th and 11th cross roads in Muneshwara layout in ward no. 03, Attur

Sl No	Description of work	Unit	No	Length m	Breadth m	Depth m	Quantity	Rate in Rs	Amount in Rs
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)								
	For RCC Drain	Cum							
	Muneshwara layout								
	8th cross, Left side		2	76.00	1.00	0.90	136.80		
	8th cross, Right side, LHS		1	263.00	1.00	1.00	263.00		
	8th cross, Right side, RHS		1	245.00	1.10	1.00	269.50		
	9th cross, Left side		2	100.00	1.00	1.00	200.00		
	9th cross, Right side		2	173.00	1.00	0.95	328.70		
	10th cross, Left side		2	45.00	1.00	0.90	81.00		
	Culvert		5	6.40	1.50	0.90	43.20		
							1322.20	220.40	291412.88
	Basic Rate Rs.=	130.00							
	Add 6% A.W Rs. =	7.80							
	Sub Total =	137.80							
	8Km Lead, Loading and Unloading =(2*1.28*10)+57	82.60							
	Total Rate Rs. =	220.40							
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222, I No-27.18)								
	For Drain	Cum							
	Muneshwara layout								
	8th cross, Left side		2	76.00	1.00	0.15	22.80		
	8th cross, Right side, LHS		1	263.00	1.00	0.15	39.45		
	8th cross, Right side, RHS		1	245.00	1.10	0.15	40.43		
	9th cross, Left side		2	100.00	1.00	0.15	30.00		
	9th cross, Right side		2	173.00	1.00	0.15	51.90		
	10th cross, Left side		2	45.00	1.00	0.15	13.50		
	Culvert		5	6.40	1.50	0.15	7.20		
							205.28	5421.90	1112980.52
	Basic Rate Rs.=	5115.00							
	Add 6% A.W Rs. =	306.90							
	Total Rate Rs. =	5421.90							

SI No	Description of work	Unit	No	Length m	Breadth m	Depth m	Quantity	Rate in Rs	Amount in Rs
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWD S.R 2018-19)								
	For RCC Drain	Cum							
	Bottom slab								
	Muneshwara layout								
	8th cross, Left side		2	76.00	0.80	0.15	18.24		
	8th cross, Right side, LHS		1	263.00	0.80	0.15	31.56		
	8th cross, Right side, RHS		1	245.00	0.90	0.15	33.08		
	9th cross, Left side		2	100.00	0.80	0.15	24.00		
	9th cross, Right side		2	173.00	0.80	0.15	41.52		
	10th cross, Left side		2	45.00	0.80	0.15	10.80		
	side walls								
	Muneshwara layout								
	8th cross, Left side		4	76.00	0.15	0.60	27.36		
	8th cross, Right side, LHS		2	263.00	0.15	0.60	47.34		
	8th cross, Right side, RHS		2	245.00	0.15	0.75	55.13		
	9th cross, Left side		4	100.00	0.15	0.60	36.00		
	9th cross, Right side		4	173.00	0.15	0.60	62.28		
	10th cross, Left side		4	45.00	0.15	0.60	16.20		
	Culvert raft		5	6.40	1.20	0.20	7.68		
	Culvert wall		10	6.40	0.23	0.60	8.83		
							420.01		
						Net Qty.	420.01	7070.20	2969568.84
	Basic Rate Rs.=	6670.00							
	Add 6% A.W Rs. =	400.20							
	Total Rate Rs. =	7070.20							
4	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebtrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWD S.R 2018-19)								
	Considering steel For Drain @ 60 kg / cum	Tonne		403.50	0.060	--	24.21		
	Considering steel For culvert @ 90 kg / cum	Tonne		16.51	0.090	--	1.49		
							25.70	73992.24	1901310.52
	Basic Rate Rs.=	69804.00							
	Add 6% A.W Rs. =	4188.24							
	Total Rate Rs. =	73992.24							

[illegible]



RCC CULVERT
RCC DRAIN

Date Rev. R0	AMS Layout in ward no. 03, Attur	Improvements to roads and drain at Cross and Main roads in	Executive Engineer	Assistant Engineer	Assistant Engineer	Assistant Engineer	Assistant Engineer	Assistant Engineer	Assistant Engineer
-----------------	----------------------------------	--	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------	--------------------

